


# Computational Research and Theory Facility (CRT)



**Jeff Broughton**  
NERSC Deputy for Operations

February 25, 2015

# CRT Located at LBNL Main Gate





- **Four story, 140,000 GSF facility for scientific computing including:**
  - 20,000+9,870 ASF High Performance Computing Floor
  - 41,000 ASF office and conference area; ~300 offices
- **\$143M UC Sponsored Building**
  - No long term commitment or decommissioning costs
  - No major capitalization or appropriations costs
- **\$19.8M DOE Funded Data Center**
  - Power and cooling expansion for NERSC systems
- **Notable Features**
  - Free cooling
  - Heat recovery
  - Seismically isolated floor

# Power and Cooling Capacity



	Move-in	Drop-in Expansion Capability
Power feeders	27MW redundant 42MW non-redundant	Same
Power Substations	5 substations @ 2.5 MW	11 = 27.5 MW
UPS	1.0+0.5 MW	2.0+1.0 MW
Generator	1 @ 1.25 MW	2 = 2.5 MW
AHUs	3+1 redundant @ 60K CFM / 0.5MW = 1.5 MW	30 = 15 MW
Cooling Towers	3+1 @ 3.375MW = 10.25 MW	6+1 = 20.25 MW
Chillers	None	2 x 550 ton



**“The coldest winter I ever spent was a summer in San Francisco.”**




# Free cooling provides exceptional energy efficiency




- **LBNL's location and the CRT design enables**
  - Power Usage Effectiveness (PUE): 1.1
  - Data Center infrastructure Efficiency (DCiE): 0.91
- **Air cooling**
  - 75°F air year round without chillers
- **Liquid cooling**
  - 74°F water year round without chillers
- **Computer room exhaust heat used to heat office floors**
- **Save ~50% per year on power costs**
  - Free cooling + WAPA power

# Building Cross Section





# CRT machine room layout



# Air handlers






# Cooling Pipes

**NERSC**






# Hot aisle containment with chimneys will facilitate energy recovery



# Seismic floor isolates systems from severe earthquakes





# Seismic Floor Installation





# Testing of Seismic Floor



# Key Strategies for the Move



- **Concurrent operation in CRT and OSF**
  - Reduce impact to users by minimizing downtime
  - Move equipment in manageable phases
  - Decouple risk associated with simultaneous moves
  - Reduce impact on staff / need for additional staff
- **Dedicated 400Gb/s inter-site network**
  - ESnet to provide wave gear and link; NERSC the routers
  - Network reduces timing dependencies – systems can access storage at either site (with some BW limits)
- **Duplicate key infrastructure to simplify the transition**
  - Time refresh/upgrade purchases to minimize cost
  - Buy early and test and stage new gear in OSF
  - Retire old gear in OSF

# Avoiding a Resource Dip



- **NERSC delivered core-hours could dip in AY15/16**
  - Edison outage over move
  - Hopper & Carver retirement
  - NERSC-8 delay and pre-production time
- **Mitigate with NERSC-8 Phase 1**
  - Plan to buy a 10-cabinet Cray XC Haswell system along with Cori File System and Burst Buffer to bridge resource loss
  - First Cray system to be installed in CRT
  - Make operational before Edison moves to cover Edison's outage
  - Will enable delivered core-hours to stay flat at the AY14 level of ~3 billion throughout the move



# Very High Level Plan



- **Install power distribution and cooling manifolds [Mar->Aug]**
- **Install networking and IB SAN infrastructure [May]**
- **Move file systems (NGF) [Jun->Oct]**
- **Install NERSC-8 Phase 1 (Hopper+) [Aug-Oct]**
- **Retire Carver at OSF by 9/30**
- **Move Edison [Oct-Nov]**
- **Retire Hopper at OSF [Dec]**
- **Install NERSC-8 Phase 2 [Spring 2016]**
- **Tape libraries will not move before late 2016**



**Thank you!**