

NERSC Machine Generations: 1st Level of EE Improvement



Edison: ~2 MW





Cori: 5x Edison, ~4 MW

Perlmutter: 3x Cori, ~6 MW







Scientific Computing Energy Efficiency



Avoid Compute Jobs failing

 A SysAdmin challenge for facilities with many users like NERSC

Site Specific Facility Design

- Dissipate HPC waste heat directly to outside environment (or another use) as much as possible, and
- avoid vapor-compression based air conditioning as much as possible
- Operational tools providing high resolution realtime performance monitoring & analysis
 - Supporting all operational activities









Four-Story 150,000 GSF


- Two 20k sf office floors, 300 offices
- 20k -> 28k sf HPC floor
- 21.5 MW
- Current demand ~10 MW

Energy Efficient

- Year-round compressor-free air and water cooling
- LEED Gold Rated Building
- High resolution monitoring
- PUE 1.08 annual avg

Room Air & Cooling Water

- Most hours, single pass air
- Cooling Towers can provide 75°F or colder water all hours of year









NERSC – Significant Energy User




At ~40% of campus energy demand, NERSC is a designated SEU and participates within the Core Team of the LBNL Energy & Water Management Program

LBNL Receives DOE's 50001 Ready & ISO 50001



Photo Credit: LBNL. Shyh Wang Hall, home of NERSC, the Lab's high performance computing center.

After nearly three years of development and implementation, <u>Lawrence Berkeley National Laboratory</u> (LBNL) received <u>DOE's 50001 Ready</u> recognition in June 2020, and was subsequently ISO 50001 certified in September 2020 with zero non-conformities. <u>ISO 50001</u> is an international standard for managing and improving energy management and DOE's 50001 Ready Program is a free, self-guided approach based on the principles of the ISO guidance. LBNL pursued 50001 as a way to ensure both its energy and water management activities and efficiency savings were strategic, effective, and persistent.







NERSC EE - LBNL Division Collaboration





Monday, Feb. 24





Groundbreaking Step Toward Efficient Data Centers

Berkeley Lab's decades of expertise in energy-efficient data centers is now being applied to NERSC resources via the Efficiency Optimization Project, a partnership between NERSC, ETA, and Sustainable Berkeley Lab that uses operational data analytics to optimize cooling systems and save electricity.





February 25, 2020

As HPC datacenters scale up, improving efficiency is crucial to avoiding correspondingly large energy use (and the ensuing high costs and large carbon footprints). Now, a team at Lawrence Berkeley National Laboratory's National Energy



Site Map | My NERSC | < S

HOME ABOUT SCIENCE AT NERSC SYSTEMS FOR USERS NEWS & PUBLICATIONS R & D EVENTS LIVE STATUS TIMELINE

NEWS & PUBLICATIONS

LESS IS MORE: LBNL BREAKS NEW GROUND IN DATA CENTER OPTIMIZATION

NERSC efficiency metrics project leverages Lab's decadeslong expertise in energy management

FERRUARY 18, 2020

Contact: Kathy Kincade, kkincade@lbl.gov, +1 510 495 2124

Finding ways to improve energy efficiency in high performance computing (HPC) data centers is not a new challenge but it is an evolving one, driven by increasing data creation, changes in the world's climate, and pressure to reduce energy consumpt and carbon footprints. Together these factors dramatically influence the design and maintenance of HPC facilities and the hardware and software resources within them

Fortunately, for decades Lawrence Berkeley National Laboratory (Berkeley Lab) has been at the forefront of efforts to design, build, and optimize energy-efficient hyperscale data centers. The Energy Technologies Area (ETA) has supported the National Energy Scientific Research Computing Center (NERSC) and other Berkeley Lab facilities on energy issues for some 30 years, according to Rich Brown, a research scientist in ETA's Building Technologies and Urban Systems Division. In 2007, for example, Berkeley Lab was lead author on a U.S. Environmental Protection Agency (EPA) study of the national impact of data center energy use and on the resulting DOE report. In addition, ETA has been involved in EPA's Energy Star program for more than 25 years, developing specifications for servers, data storage, and network equipment

"Berkeley Lab has been the lead institution in the U.S. on data center energy use research," Brown said. "ETA is an applied science division, and the mission here is to reduce the environmental impacts of energy use." Much of this work has been funded brough the Federal Energy Management Program, including a







Energy & Water Performance Tracking




- Power Usage Effectiveness (PUE)
- IT-power usage effectiveness (ITUE)
- Water Usage Effectiveness (WUE)

Total Data Center Energy / HPC Compute Equip. Energy IT Equipment Energy / Compute Components Energy Water Volume Evaporated / Cooling Plant Energy (L/kWh)

E&WMP Targets for NERSC PUE <1.1, WUE TBD

Month	PUE	Metering Uptime	Numerator, 1mo Average	Denominator, 1mo Average		
1 2020-04	1.072	99.34%	4,240kW	3,956kW		
1 2020-05	1.085	99.83%	4,269kW	3,934kW		
1 2020-06	1.096	99.86%	4,321kW	3,942kW		
1 2020-07	1.099	35.72%	4,255kW	3,871kW		
3020-08	1.134	94.93%	4,472kW	3,944kW		
1 2020-09	1.147	97.15%	4,346kW	3,790kW		
3020-10	1.139	36.63%	4,209kW	3,695kW		
1 2020-11	1.082	13.21%	4,419kW	4,082kW		
3020-12		0%				
i 2021-01	1.086	79.33%	4,294kW	3,954kW		
1 2021-02	1.074	100%	4,370kW	4,071kW		
i 2021-03	1.066	99.63%	4,278kW	4,011kW		








OMNI – Monitor and Manage










Operational Data Analytics (ODA)





- SkySpark allows us to create custom real-time data visualizations
- Fast tool for ongoing optimization






Cray XC Series - Dynamic Fan Speed Control



- Blower Cabinets (6 High Performance Fans per)
 - Variable from 2500 to 4000 rpm
 - Dynamic Fan Speed Control saves energy by sensing 5°C processor temp change (HPC load), then
 - Adjusts fan speed (entire row) up or down accordingly. Hottest processor(s) set speed on entire row
 - Command line set of a <u>Static</u> cooling coil exiting air temperature (Typ. 68 71°F)
 - hss.ini SMW file
 - Seasonal setting chosen for heat extract ratio of CW = 70 to 80%, balance to room air cooling







"Dynamic" Cabinet Air Temperature Too



Merged System & Infrastructure Data


Cori Water Valve Position

8/11

8/13

- Out of the Box operation: Static cabinet air temperature setpoint
 - Can't be set for all weather, so potential CW pumping and XC fan energy waste
- Cooling Plant Interactive Operation: Variable cabinet air temperature setpoint
 - Cooling CW Temps: Cooler cabinet air, so fan speeds turndown
 - Warmer CW Temps: Fans turn up and higher cabinet temperature setpoint reduces time at 100% open valve position, so pump savings

8/9





8/7

8/5

% Open

20



Perlmutter & NERSC-10 Facility Upgrade Design NerSC

- BIG Team provided Facility Design Input
 - Ongoing BMS Controls Review
 - Commissioning & functional testing scope and review
 - Identification of needed equipment and configuration
- Energy Efficiency considerations in Owner's Project Requirements (OPR) during design phases
- Engage with equipment vendors for targeted advanced design on components & methods





Other NERSC EE activities



ML based controls (in planning)

- CT Fans vs Pumps optimization (difficult to optimize for all seasons)
 - Cooling Water Plant COP optimization
- AlOps (HPE)

Outreach and Collaboration

- EE HPC Working Group
 - ODA Subgroup
 - Cooling Controls Subgroup
- DOE EERE Office
 - LBNL BTUS Division Data Centers CoE (datacenters.lbl.gov)
 - Federal Energy Management Program





Thank You



BUILDING INFRASTRUCTURE



Ben Maxwell, SE 4557, PMP Group Lead (510) 486-5573 | BHMaxwell@lbl.gov



Brent R. Draney Systems Integration Engineer (510) 486-5791 | BRDraney@lbl.gov



Jeff Grounds Facilities Manager (510) 486-7197 | JTGrounds@lbl.gov



Ernest Jew Assistant Facilities Manager EJew@lbl.gov



Eric Lucas Electronics Fabricator/ Installer (510) 486-7197 | ELucas@lbl.gov



Norman Bourassa Energy Performance Engineer (510) 486-502-5964 | NJBourassa@lbl.gov







National Energy Research Scientific Computing Center






Sustainable Berkeley Lab Initiative



471.6K

Maintained Efficiency Savings by Fiscal Year



OCx = Ongoing commissioning





SBL-BIG Identified EE Measures



		Energy Savings (kWh)		Water Savings (gal)		Cost Savings	PUE
	Measure Title	Estimated	Verified	Estimated	Verified	\$	Reduction
1	Install Firmware to Enable ESS Mode for UPSs		350,000		140,000	\$20,300	0.007
2	Implement Tower Water Supply Temperature Reset and Reduced Tower Water Pump Speed		380,000		N/A	\$22,040	0.008
3	Reset Cooling Water Temperature Setpoint and Enable Cray Dynamic Fan Control		275,000		110,000	\$15,950	N/A
4	Install New Heat Exchanger		760,000		300,000	\$44,080	0.016
5	Install Bypass Valves		35,000		10,000	\$2,030	0.001
6	Reset Cray Air Temperature Setpoint	200,000		80,000		\$11,600	N/A
7	Optimize Dynamic Fan Control	200,000		80,000		\$11,600	N/A
8	Install Booster Pump	240,000		100,000		\$13,920	0.005
9	Install Cold Aisle Temperature Sensors and Optimize AHU SAT and Flow Control	300,000		120,000		\$17,400	0.006
10	Install Cray Supply Air Hoods	100,000		40,000		\$5,800	0.002





Building Management System




- B59 uses the Campus standard WebCTRL system from Automated Logic Controls (ALC)
 - BACnet based, uses a graphical "Microblock" programming language
 - Allows owners & operators to manage and customize the building controls in-house
- Most WebCTRL applications are for human comfort space conditioning
 - NERSC has in-house capability to customize code to our specific HPC applications





Making HPC Cooling Water









Heat Exchangers








Tower Water Pumps





B59 ALC WebCTRL - User Interface










ALC Logic – NERSC Example









Hot Aisle Containment – Or Hot Air "Bath Tub"



- Really is a "separation" or "chimney" system, not full containment
 - Installed in stages from 2016 -2018
 - Panelized system better accommodates equipment churn
- Helps drive hot air to ceiling
 - Exhaust fans pull hot air out of the building
 - Return fans to AHUs
- Panels located at rack front
 - Provides cabling facilitation above rack without penetrations
- Stayed away from drop ceiling
 - Seismic floor connection costs
 - Fire code complications
- Why Hot instead Cold Aisle?
 - Many visitor tours of compute room, so human comfort a factor





